MICHIGAN DEPARTMENT OF CONSERVATION FORESTRY DIVISION

LAND CORNER RECORD

T. 46 N.R. 14 W

		Schoolcraft		COUNTY
DESCRIPTION OF CORNER	Section Corner common	to Sections	27-28-33-34	<u></u>
CORNER MONUMENT	1" Pipe with 4" Alumin	им Сар		
DATE MONUMENT PLACED A	MD WITHESSED <u>6-14-62</u>			
WITHESSES TO CORNER	5" Red Pine (NBT)	N 37° W	43½ links	
27	L* Red Pine (NBT)	N 10° E	31 links	
CIRCLE CORNER REGISTER	AND			

DESCRIPTION IN DETAIL AS TO NOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was replaced 2.589 chains North of a 1" Iron Pipe on R.R. R.O.W. as noted in Highway Department plans.

Former monument apparently removed.

Corner lies in ditch on North side of Highway M-28.

SURVEYOR'S SEAL

SIGNED Silly Suckles DATE 11-2-611

REGISTERED LAND SURVEYOR

Billy D. Buckler