

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 46 N. R. 14 W


Schoolcraft COUNTY

DESCRIPTION OF CORNER Section Corner common to Sections 16-17-20-21

CORNER MONUMENT 1" Pipe with 4" Aluminum Cap

DATE MONUMENT PLACED AND WITNESSED 5-31-62 with Wm. Miller, Aide

WITNESSES TO CORNER..... 8" Jack Pine (S 17 NBT) N 82° W 34 links



5" Red Pine (S 21 NBT) S 30° E 78½ links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was replaced from one W. Pine stump bearing N 75° W 29 links and one Red Pine stump bottom bearing N 38° E 46 links.

Found original W. Pine line tree 19.27 chains North of Corner. Record Distance = 19.32 chains.

Corner lies on South edge of a narrow Pine ridge.

SURVEYOR'S SEAL

SIGNED Billy D. Buckler DATE 4-2-64
REGISTERED LAND SURVEYOR
Billy D. Buckler