

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

# LAND CORNER RECORD

T. 46 N. R. 14 W


Schoolcraft COUNTY

DESCRIPTION OF CORNER Section Corner common to Sections 11-12-13-14

CORNER MONUMENT 1" Pipe with 1/4" Aluminum Cap

DATE MONUMENT PLACED AND WITNESSED 6-15-62

WITNESSES TO CORNER..... 9" Jack Pine (S 14 NBT) S 68° W 17 links



8" Jack Pine (S 12 NBT) N 65° E 71 links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner re-established by double proportionate measure from corners 1/2 mile North; 1 1/2 miles East; 3 miles South and 2 1/2 miles West.

No evidence of original Corner.

SURVEYOR'S SEAL

SIGNED Billy D. Buckler DATE 4-2-64  
REGISTERED LAND SURVEYOR  
Billy D. Buckler