

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 46 N.R. 14 W


Schoolcraft COUNTY

DESCRIPTION OF CORNER Section Corner common to Sections 21-22-27-28

CORNER MONUMENT 1" Pipe with 1/4" Aluminum Cap

DATE MONUMENT PLACED AND WITNESSED 6-18-62

WITNESSES TO CORNER..... 13" Red Pine (S 21 NBT) N 38 W° 23 links



12" Red Pine (S 27 NBT) S 73 E° 152 1/8 links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Corner lies $5\frac{1}{4}$ links West of Road.

This Corner re-established by double proportionate measure from Corners 1 mile South;
2 miles West; $2\frac{1}{2}$ miles North and 3 miles East.

No evidence of original Corner.

SURVEYOR'S SEAL

SIGNED Billy D. Buckler DATE 4-2-64
REGISTERED LAND SURVEYOR
Billy D. Buckler