

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

| | | |
|------------------------------------|---------------------------|---------------|
| Schoolcraft | Located In: | Corner Code # |
| (County) | | |
| 1. Public Land Survey | T <u>46N</u> R <u>14W</u> | <u>I7</u> |
| | T <u>46N</u> R <u>14W</u> | <u>J7</u> |
| | T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Oct 06 2003

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- (I7) Corner common to Sections 14-15-22-23. 1962: Billy D. Buckler reestablished the corner midway and on line between two Section corners. Set 1" pipe with 4" aluminum cap. No witnesses.
- (J7) Quarter corner common to Sections 14-23. 1962: Billy D. Buckler RLS reestablished the corner midway and on line between Section corners. Set 1" I.pipe with 4" aluminum cap. 6" J.Pine N50E 43 links, 8" J.Pine S72E 73 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (I7) Found the 1962 monument in good condition. The 1962 position for the corner is not accepted due to the reestablishment by the undersigned of Section corners I5, K7, and M7 upon which the position of this corner depends. I reestablished the corner by double proportionate measure to the original record between Quarter corner 8023.84' North, Section corner 10582.89' West, Section corner 10568.03' South, and Section corner 10582.60' East. From the corner thus established, the 1962 position, now destroyed, is S89W 31.96' distant. Drove the 1962 monument at the reestablished position. Found no evidence of the original 1850 bearing trees.
- (J7) Found the 1962 monument in good condition and at record bearing and distance from the 1962 witnesses, both dead but standing. The distances to these trees appears to have been transposed on the 1962 record. The 1962 position for the corner is not accepted due to the reestablishment by the undersigned of Section corners I7 and K7. I reestablished J7 midway and on a line of mean true bearing between these two corners, which are 2645.74' West and East. From the position thus established, the 1962 position is S79W 40.89' distant. I used the 1962 trees for new witnesses, as described below. Found no evidence of the original 1850 bearing trees.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|--|--|
| (I7) Set 1" IDx36" I.pipe with 4" brass MDNR cap. Blazed, scribed, and set measuring nails in: | (J7) Set 1" IDx36" I.pipe with 4" aluminum MDNR cap. Set measuring with tags in: |
| 5" Cherry S64W 12.2' "S22 NBT" | 6" J.Pine N07W 26.3' * |
| 8" Cherry S82W 56.4' do | 8" J.Pine S54W 19.1' * |
| 4" Cherry N82W 19.4' "S15 NBT" | 10" J.Pine N60W 48.4' |
| 3" J.Pine S76E 42.85' nail/tag only | 6" J.Pine N39E 24.5' |
- Bearings are magnetic. Distances are to nail with tag. The corner falls on the south side of a ditch.
- All four of these trees are dead. No living trees in the area. Bearings are magnetic. Distances are to nail with tag.



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 11/18/03

For the Michigan Department of Natural Resources, Office of Land and Facilities