

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in  
Schoolcraft

(County)

Located In:

Corner Code #

1. Public Land Survey	T <u>46N</u> R <u>14W</u>	<u>K11</u>
	T <u>    </u> R <u>    </u>	<u>    </u>
	T <u>    </u> R <u>    </u>	<u>    </u>
	T <u>    </u> R <u>    </u>	<u>    </u>
2. Property Controlling in Section	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
3. Miscellaneous Property in Sec.	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

Mar 09 2004

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 19\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:  
(K11) Corner common to Sections 25-26-35-36. 1850: Established by Guy H. Carleton, Deputy Surveyor: Set [temporary] post 25,26,35,36. Tamarac 5 N22W 44 links, Tamarac 5 S44E 152 links. (My copy of Carleton's notes include the word "temporary" at the bracketed position shown above. I believe that this is an error, either in the transcription or in the original record, and that the word "temporary" does not belong here in the record). 1956: MSHD plans for State Highway M-28 show 1 1/4" I.pipe 216.03' north of the centerline of the highway at Sta. 1578+80.06 forming an angle in the NE quadrant of 90deg.33'15" with the highway C/L. Witnesses: 3" Poplar N78W 41.33', 4" N.Pine N55W 82.88', 3" Poplar N41W 83.13'. 1961: Billy D. Buckler recorded the corner: 1 1/4" iron pipe. This corner was recorded as set by M.S.H.D. Corner lies 106.9' north of C/L M-28. 9" Y.Pine (N8T) N57W 82.1'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(K11) The original post and accessories were not recovered. The 1 1/4" pipe monument of record was found disturbed by road or ditch construction, buried in fill in the immediate vicinity of the position subsequently reestablished. Reestablished the corner as follows: 1) at record bearing and distance from the measuring notch of Buckler's Y.Pine N8T, now 18" dia. in good condition. This N8T is certainly the same tree described as "N.Pine" in the 1956 MSHD record and the MSHD distance fits to the center of the tree (no meas. nail found). 2) at the Buckler's 1961 distance north of the centerline of M-28 as I reconstructed it by applying the MSHD 1956 plan data referenced to corners I11, K11, and M11, and a 2" bolt at the RR R/W South of K11. 3) The record MSHD angle, noted above, to K11 from the reconstructed highway C/L. The MSHD distance from the C/L to K11 (216.03') must certainly be in error. From the corner thus established, distances to I11 and M11 are 0.7' and 40.2' longer than the GLO record, respectively, and K11 is 3.8' South of a straight line between them. The position herein described was used to reestablish certain corners in and around Sections 13 and 14, T46N-R14W, in the autumn of 2003 and has only recently been monumented.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(K11) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Blazed, scribed, and set measuring nails in:  
10" R.Pine N27W 59.3'  
8" J.Pine N84W 49.75'  
6" J.Pine N72W 50.1'  
18" R.Pine N55W 82.65' (the 1961 N8T)  
Bearings are magnetic. Distances are to nail with tag. The mon. lies east of a ditch.



Signed by Stephan J. Szyszkoski  
Surveyor's Michigan License No. 33986

Date 4/8/04