

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Schoolcraft</u> (County)	Located In:	Corner Code #	
1. Public Land Survey	T <u>46N</u> R <u>14W</u>	<u>16</u>	
	T _____ R _____	_____	_____
	T _____ R _____	_____	_____
2. Property Controlling in Section	S _____ T <u>46N</u> R <u>14W</u>	<u>2</u>	
	S <u>14</u> T _____ R _____	_____	_____
	S _____ T _____ R _____	_____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____	_____
	S _____ T _____ R _____	_____	_____
4. Lot No. _____, Recorded Plat _____			
5. Private Claims	16 Oct 06 2003		
	2 Oct 02 2003		

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(16) Quarter corner common to Sections 14-15. 1962: Billy D. Buckler RLS reestablished the corner midway and on line between Section corners. Set 1" I.pipe with 4" aluminum cap. 9" Jack Pine N52W 26.5 links, 7" Jack Pine N54E 13 links.
 (2-Sec. 14) East 1/16 corner between Sections 11-14. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(16) The 1962 monument and accessories were not recovered. The 1962 position for the corner is not accepted due to the reestablishment by the undersigned of Section corners I5 and I7, upon which the location of this corner depends. Reestablished the corner midway and on a straight line between these two corners, which are 2674.47' North and South. Found no evidence of the original 1850 bearing trees.
 (2-Sec. 14) Established the corner midway and on a line of mean true bearing between Quarter corner 1309.08' West and Section corner 1309.08' East.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(16) Set 1" IDx36" I.pipe with 4" aluminum MDNR cap. Blazed, scribed, and set measuring nails in:	(2) Set 1" IDx36" I.pipe with 4" aluminum MDNR cap. Blazed, scribed, and set measuring nails in:
6" J.Pine N40W 7.35'	12" Spruce S51W 81.2'
5" W.Birch N26E 10.65'	14" R.Pine S45W 116.5'
6" J.Pine S40W 6.5'	5" Spruce N89W 70.5'
10" Spruce S84E 33.2'	3" Spruce N09E 47.45'
Set a cedar post adjacent. Bearings are magnetic. Distances are to nail with tag.	Set a cedar post adjacent. Bearings are magnetic. Distances are to nail with tag.



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 11/18/03

For the Michigan Department of Natural Resources, Office of Land and Facilities