

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

Schoolcraft	Located In:	Corner Code #
<small>(County)</small>		
1. Public Land Survey	T <u>    </u> R <u>    </u>	<u>          </u>
	T <u>    </u> R <u>    </u>	<u>          </u>
	T <u>    </u> R <u>    </u>	<u>          </u>
	S <u>    </u> T <u>    </u> R <u>    </u>	<u>          </u>
2. Property Controlling in Section	S <u>13</u> T <u>46N</u> R <u>14W</u>	<u>3</u>
	S <u>13</u> T <u>46N</u> R <u>14W</u>	<u>5</u>
3. Miscellaneous Property in Sec.	S <u>    </u> T <u>    </u> R <u>    </u>	<u>          </u>
	S <u>    </u> T <u>    </u> R <u>    </u>	<u>          </u>

4. Lot No.           , Recorded Plat           

5. Private Claims

5	Sep 29 2003
3	Oct 02 2003

I, Stephan J. Szyszkoski, in a field survey on           , 20     do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

- (3-Sec. 13) North 1/16 corner between Sections 13 and 14. Not established in the original survey. Established ca. 1964 by the Michigan DNR, not of record, and monumented with a 1"ID iron pipe with 4" brass cap, unmarked.
- (5-Sec. 13) North 1/16 corner Section 13. Not established in the original survey. Found no other record.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

- (3-Sec. 13) Established the corner midway and on a straight line between Section corner 1326.17' North and Quarter corner 1326.17' South. From the corner thus established, found a "t"-type iron fence post S88W 64.1' distant. Removed the ca. 1964 monument and reinstalled it at the corner position established.
- (5-Sec. 13) Established the corner midway and on a straight line between Quarter corner 1324.60' North and Center of Section 1324.60' South. From the corner thus established, found a "t"-type iron fence post S57E 59.85' distant.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

- |  |  |
|--|--|
| (3) Set 1"IDx36" I.pipe with 4" brass MDNR cap. Blazed, scribed, and set measuring nails in: | (5) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Blazed, scribed, and set measuring nails in: |
| 4" J.Pine N19W 6.7' "N1/16 BT"   | 6" J.Pine S73E 98.75' "N1/16 BT"   |
| 5" J.Pine N81E 17.65' do   | 8" J.Pine S07E 41.7' do  |
| 14" Spruce S12E 38.3' do   | 10" J.Pine S45W 53.15' do  |
| 12" Spruce S85W 49.15' do  | 12" J.Pine S69W 63.9' do   |
- Set a cedar post adjacent. Bearings are magnetic. Distances are to nail with tag.
- Bearings are magnetic. Distances are to nail with tag.

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													



Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 11/18/03