

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Schoolcraft	Located In:	Corner Code #
(County)		
1. Public Land Survey	T <u>46N</u> R <u>14W</u>	<u>M5</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Aug 25 2003

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(M5) Corner common to Sections 12-13 T46N-R14W and 7-18 T46N-R13W. 1962: Corner reestablished by Billy D. Buckler RLS: "This corner was reestablished by double proportionate measure from corners 1 mile North; 1/2 [mile] East; 3 miles South and 3.5 miles West. No evidence of original Corner. Set 1" pipe with 4" aluminum cap. 9" Jack Pine S35W 90 links, 6" Jack Pine S30E 64 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(M5) Recovered the 1962 monument in good condition and at record bearing and distance from the J.Pine witness S30E. A reexamination of the original record and the 1962 survey notes led me to conclude that the proper position for this corner, in the absence of immediate physical evidence of the original corner itself, of which none was recovered, is 92.46' easterly from the 1962 position, being on the range line as monumented on the ground by recorded corners M3 and M11 and at the proportionate distance between those two corners. Accordingly, I reestablished and monumented the corner at that position. From the corner thus established, the original corner at F5 is 280.71 chains west (280.93 chains GLO) and the line call "leave bottom" 17.50 ch. west of M5 checks very well with the record. I believe that the distance between M5 herein described and C5 of T46N-R13W, another original corner, used indirectly by Mr. Buckler to reestablish M5, was not reported correctly in the original 1850 field notes by Guy Carlson, D.S. (77.60 ch. M, 79.50 ch. R) and should not have been used by Mr. Buckler to reestablish M5 as he did. From M5 thus reestablished, the bearing of the Range line was observed to be N00 deg. 04' 16"E. I destroyed the 1962 monument and remaining accessory.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(M5) Set 1" IDx36" I.pipe with 4" alum.

MDNR cap. Blazed, scribed, and set

measuring nails in:

- 10" W.Pine S03E 7.6' "S18 NBT"
- 8" J.Pine S78W 21.2' "S13 NBT"
- 8" W.Pine N40W 34.55' "S12 NBT"
- 12" W.Pine N06E 15.8' "S7 NBT"

Set a Cedar post adjacent. Bearings are magnetic. Distances are to nail with tag.

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													



Signed by Stephan J. Szyszkoski Date 11/18/03
 Surveyor's Michigan License No. 33986