

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Schoolcraft</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>46N</u> R <u>14W</u>	<u>F3</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3						●							
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

Sep 27 2006

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(F3) Quarter corner common to Sections 4 and 9. 1956 - Perpetuated by Billy D. Buckler RLS: "Re-witnessed 1/4 corner as set by John Brotherton, Surveyor. One Hemlock B.T. in good condition. 1" axle shaft with 6" cap in place" Witnesses: 15" White Pine N88W 160.5 links, 36" W.Pine stump N60E 39 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(F3) The 1956 monument was found laying on the ground, disturbed, adjacent to a full length wood post, both extracted by persons unknown. The original Hemlock BT noted in the 1956 record was not recovered. The 1956 W.Pine stump witness was not recovered, having likely been removed by road construction. The 1956 W.Pine NW is now a cut stump with no markings visible. Recovered the likely original position of the 1956 monument by finding indentation in the soil, soil disturbance, and woody debris with orange paint below the surface. This position is at record bearing and distance from the stump remains of the 1956 W.Pine NW. Replanted the 1956 monument at the recovered position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(F3) Set 1" axle shaft with 6" cap. Set measuring nails in:
 18" W.Pine N30E 53.25' mrkd "1/4S N8T"
 19" W.Pine N52W 49.23' do
 15" W.Pine S22W 53.02' do
 18" R.Pine East 93.71' do
 Bearings are magnetic. Distances are to nail with tag.

Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 12/28/06