

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Schoolcraft</u> <small>(County)</small>	Located In:	Corner Code #	
1. Public Land Survey	T <u>46N</u> R <u>14W</u>	<u>F4</u>	
	T _____ R _____	_____	
	T _____ R _____	_____	
2. Property Controlling in Section	S _____ T <u>46N</u> R <u>14W</u>	<u>8</u>	
	S _____ T _____ R _____	_____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	
4. Lot No. _____, Recorded Plat _____			
5. Private Claims	8 Oct 02 2006		
	F4 Nov 13 2006		

Register of Deeds Stamp & File
Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		●		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on _____, 20__ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- (F4) Center of Section 9. Not established in the original survey.
- (8-Sec. 9) West 1/16 corner, Section 9. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (F4) Established the corner at the intersection of straight lines connecting opposite 1/4 corners.
- (8-Sec. 9) Established the corner midway and on a straight line between Quarter corner 1317.14' west and Center of Section 1317.14' east.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(F4) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nails in:	(8) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nails in:
8" Hemlock S37E 33.85' mrkd "CS BT"	19" W.Pine S59E 20.3' mrkd "W1/16 BT"
10" Hemlock N86W 42.75' do	10" Hemlock N76E 17.6' do
10" W.Pine N49W 23.5' do	9" Maple N39W 16.78' do
12" Maple N50E 45.2' do	10" Maple S58W 17.08' do
Bearings are magnetic. Distances are to nail with tag.	Bearings are magnetic. Distances are to mail with tag.



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 12/28/06

For the Michigan Department of Natural Resources, Office of Land and Facilities