

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Schoolcraft</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>46N</u> R <u>14W</u>	<u>G3</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S <u>9</u> T <u>46N</u> R <u>14W</u>	<u>1</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims

G3 Sep 27 2006
 1 Oct 06 2006

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(G3) Corner common to Sections 3-4-9-10. 1960 - Remonumented from two probable original B.T. stumps by Billy D. Buckler RLS. Set 1" I.pipe with 4" brass cap. Witnesses: 15" W.Pine N65W 41 links, 13" W.Pine N35E 38.5 links.
 (1-Sec. 9) West 1/16 corner between Sections 4 and 9. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(G3) Found the 1960 monument in good condition and at record bearing and distance from the 1960 witnesses, both in good condition. The OBT stumps noted in the 1960 record are both gone. Left the monument in place and made new witnesses. The corner lies on the N. side of an E-W trail and in line with a trail to the south.
 (1-Sec. 9) Established the corner midway and on the Section line between Section corner 1323.50' west and Quarter corner 1323.50' east.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(G3) Found 1" ID I.pipe with 4" brass cap. Set measuring nails in:	(1) Set 1" IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nails in:
30" W.Pine N60W 27.8' mrkd "S4" *	7" Hemlock N84W 9.34' mrkd "W1/16 BT"
22" W.Pine N38E 25.65' "S3" *	7" Hemlock N10W 6.92' do
11" twin R.Pine S24E 76.15' "S10 NBT"	9" Hemlock S74E 11.62' do
19" R.Pine S33W 77.75' "S9 NBT"	6" twin Hemlock S23E 17.19' do
Bearings are magnetic. Distances are to nail with tag. * denotes 1960 NBT.	Bearings are magnetic. Distances are to nail with tag.



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 12/28/06

For the Michigan Department of Natural Resources, Office of Land and Facilities