

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Schoolcraft</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>46N</u> R <u>14W</u>	<u>G4</u>
	T <u>46N</u> R <u>14W</u>	<u>F5</u>
	T _____ R _____	_____
	S _____ T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Sep 27 2006

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- (G4) Quarter corner common to Sections 9 and 10. 1960 - Corner remonumented from the rotted remains of a W.Pine stump (probable 8.T.) by Billy D. Buckler RLS. Set 1" pipe with 4" brass cap. Witnesses: 18" R.Pine N08W 75 links, 7" R.Pine N54E 25 links.
- (F5) Quarter corner common to Sections 9 and 16. 1956 - Remonumented by Billy D. Buckler RLS from two Pine 8.Ts, one in good condition, one poor. Set 1" pipe with 4" brass cap. Witnesses: 15" R.Pine S57W 21 links, 16" R.Pine N85E 96 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (G4) Found the 1960 monument in good condition and at record bearing and distance from the 1960 witnesses. The R.Pine NW is now a stump. The R.Pine NE is in good condition. Left the monument in place and made new witnesses.
- (F5) Recovered the 1956 monument in good condition and at record bearing and distance from the 1956 witnesses, both in good condition with old markings visible. The original Pine 8Ts noted in the 1956 record are both down. Left the monument in place and made new witnesses.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|--|---|
| (G4) Found 1"ID I:pipe with 4" brass MI Dept. of Conservation cap. Set measuring nails in:
18" R.Pine N60E 16.7' mrkd "1/4S" *
18" R.Pine N03E 13.2' "1/4S NBT"
12" R.Pine S78W 16.3' do
12" R.Pine S31E 42.05' do
Bearings are magnetic. Distances are to nail with tag. * denotes 1960 NBT. | (F5) Found 1"ID I:pipe with 4" brass MI Dept. of Conservation cap. Set measuring nails in:
18" R.Pine S57W 14.1' old marks *
22" R.Pine N89E 63.65' do *
12" R.Pine N52E 21.75' mrkd "1/4S NBT"
6" W.Pine N78W 19.44' do
Bearings are magnetic. Distances are to nail with tag. * denotes 1956 NBTs. |
|--|---|

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9	●	10		11		12	
5						●							
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 12/28/06

For the Michigan Department of Natural Resources, Office of Land and Facilities