

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 46 N. R. 15W


Schoolcraft COUNTY

DESCRIPTION OF CORNER Section corner for 18 | 17

CORNER MONUMENT 1" Iron pipe with 4" Brass Cap.

DATE MONUMENT PLACED AND WITNESSED 8-28-61

WITNESSES TO CORNER..... 7" Black ash (S17 NBT) N25°E 10½ links



9" Cedar (S19 NBT) S54°W 21 links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was replaced from 2 tamarack B.T.'s (Tamarack 10" N19°W 22 links) and (Tamarack N61°E 08 links). The latter seems to err in distance which should be 33 links if Bearings are to remain correct.

SURVEYOR'S SEAL

SIGNED Billy D. Buckler DATE January 2, 1962
REGISTERED LAND SURVEYOR
Billy D. Buckler