

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 46 & 47 N.R. 25 W


Schoolcraft COUNTY

DESCRIPTION OF CORNER E 1/16 Corner for Secs. 3, T46N R15W & 34, T47N R15W

CORNER MONUMENT 1" Iron Pipe with 4" Aluminum Cap

DATE MONUMENT PLACED AND WITNESSED 9/18/64 with Miller

WITNESSES TO CORNER..... 10" Beech (E 1/16 BT), N 74° E, 17 Lks.



8" Beech (E 1/16 BT), S 19° W, 43 Lks.

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This Corner was placed midway and on line between 1/4 Corner to West and Section Corner to East.

SURVEYOR'S SEAL

SIGNED Frank J. Bray DATE 10/14/1964
REGISTERED LAND SURVEYOR