

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 46 NR. 15 W.

Schoolcraft COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 22, 23, 26, 27

DESCRIPTION OF CORNER MONUMENT 1" Pipe with 4" Brass Cap

WITNESSES TO CORNER 9" Maple (S 22 NBT) N 30° W 97 1/2 Links

5" Cedar (S 23 NBT) N 84° E 63 1/2 Links

4" W. Birch (S 27 NBT) S 48° W 12 Links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED. This corner was replaced from two Tamarack Stump. (6" Tamarack S 14° E, 27 Links) iron marks plainly visible (14" Tamarack S 48° W, 14 links) badly burned but in proper direction and distances. Point of post found in ground.

Corner was placed and witnessed August 24, 1960.

SURVEYORS SEAL

SIGNED

Billy D. Buckler
REGISTERED LAND SURVEYOR

Billy D. Buckler

DATE 9/15/60