

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 46. NR. 15. W

Schoolcraft COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 8, 9, 16 & 17

DESCRIPTION OF CORNER MONUMENT 1" Pipe with 4" Brass Cap

WITNESSES TO CORNER 11" W. Pine (S 9 NBT) N 29° E 55 Links

10" Hemlock (S 8 NBT) N 31° W 43 1/2 Links

10" Soft Maple (S 16 NBT) S 34° E 57 Links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED. This corner was re-established by Double proportionate Measure from Corners 1 mile south; 1 mile west; 1/2 mile North; and 1/2 mile East. Found many blases in vicinity by no positive evidence of corner.

Corner was placed and witnessed July 22, 1960 with Frank J. Bray.

SURVEYORS SEAL

SIGNED

Billy D. Buckler
REGISTERED LAND SURVEYOR

Billy D. Buckler

DATE 7/28/60