

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 46 N.R. 15 W.


Schoolcraft COUNTY

DESCRIPTION OF CORNER Section Corner common to Sections 11, 12, 13, and 14.

CORNER MONUMENT 1" Pipe with 4" Aluminum Cap.

DATE MONUMENT PLACED AND WITNESSED 6/20/63

WITNESSES TO CORNER..... 6" W. Pine (S. 12 N.B.T.) N. 38° E. 16 Lks.



18" W. Pine (S. 14 N.B.T.) S. 65° W. 79 Lks.

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This Corner was replaced by proportioned distance East and West
and facing old blazes on a nearby down Tamarack.

No positive evidence of Original Corner.

SURVEYOR'S SEAL

SIGNED Billy D. Buckler DATE 7-29-63
REGISTERED LAND SURVEYOR
Billy D. Buckler