

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 46 N.R. 15W.


Schoolcraft COUNTY

DESCRIPTION OF CORNER $\frac{1}{4}$ Cor. bet. Secs. 13 and 24.

CORNER MONUMENT 1" Pipe with 4" Aluminum Cap.

DATE MONUMENT PLACED AND WITNESSED 6-20-63.

WITNESSES TO CORNER..... 24" W. Pine Stp. (N.B.T.) S. 84° E., 54 Lks.



15" W. Pine Stp. (N.B.T.) N. 34° W., 53 Lks.

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was re-established midway and on line bet. Sec. Cors.
Found a pine stump with face and notch bearing N. 34° W., 53 Lks.
This is a witness of a later date than the original survey. Face
is facing the re-established corner. Placed location Poster 2.00
Chs. West on Road.

SURVEYOR'S SEAL

SIGNED Billy D. Buckles DATE 10/11/63
REGISTERED LAND SURVEYOR