

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Schoolcraft
(County)

1. Public Land Survey	Located In: T46N R 15N	Corner Code # 07
	T R	
	T R	
	T R	
2. Property Controlling In Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Apr 20 1998

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	10	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:
(07) Quarter corner common to Sections 17-20. Corner established in 1850 by Guy H. Carleton: "40.11 Set quarter section post. Hemlock 17 S42W 41 links, Hemlock 22 N58W 17 links."

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
(07) Original post and accessories were not recovered. Found no evidence of the position of the original corner on the ground. Reestablished the corner midway and on a line of mean true bearing between Section corners 2655.91' East and West. At the position for the corner, I placed a 1" ID. x 36" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped. Corner placed and witnessed by T.Stark and M.Feldpausch, Newberry District Office.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
(07) Set 1" pipe with 4" MDNR cap.
Blazed, scribed, and set measuring nails in the following:
5" Balsam West 9.15' "1/4S NBT"
5" Maple N63W 28.05' "1/4S NBT"
4" Maple N89E 38.25' "1/4S NBT"
6" Maple S12W 11.3' "1/4S NBT"
Placed a 4" squared and scribed cedar post 3 ft. NW of the monument. Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date 7/29/98
Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources - Forest Management Division