

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Schoolcraft</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>46</u> N R <u>15</u> W	<u>E 9</u>
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Stephan J. Szyszkoski, in a field survey on March 14, 2007 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 (E9) Corner common to Sections 20-21-28-29. 1850 - Established by Guy Carleton Deputy Surveyor. Set post. W.Pine 10 S30W 4 links, Y.Pine 11 N39E 54 links. 1960 - Remonumented by Billy D. Buckler RLS "from one W.Pine and one Y.Pine stump. Scribe marks visible on Yellow Pine". Set 1" pipe with 4" brass cap. 8" Cedar S40W 47 links, 12" W.Pine S37E 66 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 (E9) Found the 1960 monument in good condition and at record bearing and distance from the 1960 NBTs, both now stumps. Also recovered the stump remains of the original BTs at record bearing and distance, no marks visible. Accepted the monument as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 (E9) Found 1" ID I.pipe with 4" brass MI Dept. of Conservation cap. Set measuring nails with MDNR tag in the sides of the following trees:
 6" Maple in clump N85E 8.45' mrkd "S21 NBT"
 7" Cedar S32W 33.85' "S29 NBT"
 7" Tamarack N30W 37.7' "S20 NBT"
 5" Cedar N83W 19.0' "S20 NBT"
 Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date 10/10/07

Surveyor's Michigan License No. 33986