

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Schoolcraft</u> (County)	Located In:	Corner Code #
1. Public Land Survey	<u>T46N R 15W</u>	<u>E10</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
4. Lot No. <u> </u> , Recorded Plat <u> </u>		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on Sept. 25, 2007 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
(E10) Quarter corner common to Sections 28 and 29. 1850 - Established by Guy Carleton, Deputy Surveyor, midway and on the Section line between Section corners 40.26 chains north and south. Tamarack 5 N35E 13 links, Spruce 4 S83W 12 links. 1960 - Reestablished by Billy D. Buckler RLS midway and on line between Section corners. Set 1" pipe with 4" brass cap. 6" Tamarack N45W 24 links, 5" Spruce N41E 35 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
(E10) The original post and accessories were not recovered. The 1960 monument was not recovered. The Spruce NBT was not recovered. Found the Tamarack NBT standing dead. Reestablished the corner midway and on the Section line between Section corners 2647.06' north and south.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
(E10) Set 1"IDx36" I.pipe with 4" alum. MDNR cap.
Set measuring nails with MDNR tags in the sides of the following trees:
12" J.Pine N59W 36.7' mrkd "1/4S NBT"
20" W.Pine N21W 37.95' do
6" Tamarack N28E 37.85' do
3" W.Birch N85E 8.23' do
Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date 10/10/07

Surveyor's Michigan License No. 33986