

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Schoolcraft</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T46N R 15W	F 9
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File
Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9						●							
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on September 19, 2007 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 (F9) Quarter corner common to Sections 21 and 28. 1850 - Established by Guy Carleton, Deputy Surveyor, midway and on the Section line between Section corners 40.305 chains east and west. Set post. Fir 4 S44W 7 links, Fir 6 N23E 11 links. 1960 - Reestablished by Billy D. Buckler RLS midway and on line between section corners. Set 1" ID I.pipe with 4" brass cap. 5" Aspen S23W 43 links, 6" Aspen N57E 52 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 (F9) Recovered the 1960 monument in good condition. The 1960 NBTs were not found. Verified the position of the corner and found it to be N77E 0.98' from the proportionate position intended in 1960. Accepted the monument as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 (F9) Found 1" ID I.pipe with 4" brass MI Dept. of Conservation cap. Set measuring nails with MDNR tags in the sides of the following trees:
 3" Maple S87W 46.61' mrkd "1/4S NBT"
 2" Maple S59E 16.56' no markings
 4" Spruce S86E 26.24' mrkd "1/4S NBT"
 5" Tamarack N64E 33.96' do
 Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date 10/10/07

Surveyor's Michigan License No. 33986