

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Schoolcraft Located In: Corner Code #
 (County)

1. Public Land Survey T46N R 15W F11
 T R
 T R
 S T R

2. Property Controlling S T R
 in Section S T R

3. Miscellaneous S T R
 Property in Sec. S T R

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Register of Deeds Stamp & File Number

I, Stephan J. Szyszkoski, in a field survey on Sept. 19, 2007 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 (F11) Quarter corner common to Sections 28 and 33. 1850 - Established by Guy Carleton, Deputy Surveyor, midway and on the Section line between Section corners 40.215 chains east and west. Set post. Spruce 8 N55W 3 links, Spruce 6 S35E 16 links. 1961 - recovered and recorded by Billy D. Buckler, RLS: This corner was recorded as set by M.S.H.D. Corner lies 85.0' north of c/l M-28. Found 2" iron pipe with 4" brass State of Michigan cap. 10" J.Pine North 16.4', 11" J.Pine N44W 20.4', Hwy. Dept. Witness: 6" J.Pine N40E 12.95'. Undated sketch from Michigan Dept. of Transportation shows the corner to be a 2" iron pipe with brass cap 85.02' north of the C/L of the highway and gives measurement information sufficient to allow calculation of distances 2668.66' west to Section corner and 2687.47' east to Section corner.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 (F11) The original post and accessories were not recovered. The MDSH monument was recovered near the corner position, disturbed, lying horizontally on the surface of the ground. None of the record witnesses were recovered. Reestablished the corner proportionate to the position given in old M.S.H.D. plans, by reconstructing the highway C/L (ca. 1950) using given stations and offsets from corners E11 and G11, both recovered undisturbed, and then proportioning the stationing between those section corners and applying the offset given for this corner. The current centerline of highway M-28 is 87.5' south.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 (F11) Set 2" iron pipe with 4" brass State of Michigan cap (the monument noted in the 1961 record)
 Set measuring nails with MDNR tags in the sides of the following trees:

- 8" R.Pine N47E 30.1' mrkd "1/4S NBT"
 - 13" J.Pine S85E 26.06' do
 - 8" R.Pine N25E 6.36' do
 - 6" J.Pine S78W 2.43' do
- Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date 10/10/07

Surveyor's Michigan License No. 33986