

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Schoolcraft

(County)

Located In:

Corner Code #

- | | | | | | | |
|------------------------------------|---|------------|---|------------|-----------|-------|
| 1. Public Land Survey | T | <u>46N</u> | R | <u>15W</u> | <u>G3</u> | |
| | T | _____ | R | _____ | _____ | |
| | T | _____ | R | _____ | _____ | |
| | T | _____ | R | _____ | _____ | |
| 2. Property Controlling in Section | S | _____ | T | _____ | R | _____ |
| | S | _____ | T | _____ | R | _____ |
| 3. Miscellaneous Property in Sec. | S | _____ | T | _____ | R | _____ |
| | S | _____ | T | _____ | R | _____ |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Jun 01 2005

I, Stephan J. Szyszkoski, in a field survey on _____, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

(G3) Corner common to Sections 3-4-9-10. Remonumented in 1954 by Billy D. Buckler RLS: "This corner was pointed out to me by Carl Lensi, of Northwestern Lumber Co., One original 8.I. still in place, in excellent condition. Corner was placed and witnessed July 29, 1954". Corner monument: 1" Pipe with 4" Brass cap. Witnesses: 8" Hemlock N15W 24 links, 16" Beech N70E 61 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(G3) Recovered the 1954 monument in good condition and at record bearing and distance from the 1954 witnesses. The Hemlock NW is in good condition. The Beech NE has a broken top, upper blaze is visible, lower blaze has rotted out. Made new top blaze and scribing on the Hemlock NW and made three new witnesses as described below.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(G3) Found 1" ID I.pipe with 4" brass cap. Set measuring nails in:
 12" Hemlock N11W 16.5' "S4" *
 14" Hemlock N85W 3.75' "S4 NBT"
 4" Y.Birch S83E 10.9' "S10 NBT"
 5" Maple S23W 30.25' "S9 NBT"
 Bearings are magnetic. Distances are to nail with tag. * denotes 1954 NBT



Signed by Stephan J. Szyszkoski Date 1/9/06
 Surveyor's Michigan License No. 33986
 For the Michigan Department of Natural Resources