

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Schoolcraft

(County)

Located In:

Corner Code #

1. Public Land Survey	T	<u>46N</u>	R	<u>15W</u>	<u>G5</u>
	T	<u>46N</u>	R	<u>15W</u>	<u>G1</u>
	T	_____	R	_____	_____
	T	_____	R	_____	_____
2. Property Controlling in Section	S	_____	T	_____	R
	S	_____	T	_____	R
3. Miscellaneous Property in Sec.	S	_____	T	_____	R
	S	_____	T	_____	R

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Jun 01 2005

I, Stephan J. Szyszkoski, in a field survey on _____, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

(G5) Corner common to Sections 9-10-15-16. Remonumented in 1954 by Billy D. Buckler RLS: "This corner was pointed out to me by Carl Lensi, of the Northwestern Lumber Co. One original B.T. still in place, fair condition. Corner was placed and witnessed July 29, 1954". Corner monument: 1" pipe with 4" brass cap. Witnesses: 9" Soft Maple S55W 36 links, 10" Beech S60E 17 links.
 (G1) Corner common to Sections 3-4 T46N-R15W and 33-34 T47N-R15W. Remonumented in 1964 by Frank J. Bray, RLS at the position of a "wood post set by Registered Land Surveyor Radcliff". Corner monument: 1" Iron pipe with 4" aluminum cap. Witnesses: 15" S.Maple S49W 26.5 links, 10" Beech N55E 57.5 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(G5) Recovered the 1954 monument, top part bent over but base in place and plumb and at record bearing and distance from the 1954 witnesses. The Soft Maple is in good condition, the Beech is standing with bottom face rotted out but in otherwise good condition. Made new markings on the 1954 witnesses and marked two new trees, as described below. Replaced the 1954 monument with a new one. Corner lies about 100' west of a N-S road.
 (G1) Recovered the 1964 monument in good condition and at record bearing and distance from the 1964 witness trees. The Maple is in good condition, the Beech has been cut. Left the monument in place, made new markings on the 1964 Maple, and made three new bearing trees, as described below. The corner lies about 45' east of a N-S road.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(G5) Set 1"x36" I.pipe with 4" alum. MDNR cap. Set measuring nails in:
 14" Soft Maple S60W 23.92' "S16" *
 14" Beech S55E 11.65' "S15" *
 6" Cherry N70W 12.6' "S9 NBT"
 7" Maple S07W 9.18' "S15 NBT"
 Bearings are magnetic. Distances are to nail with tag. * denotes 1954 NBT.

(G1) Found 1"ID I.pipe with 4" alum. MDNR cap. Set measuring nails in:
 20" Soft Maple S52W 17.6' "S4" *
 5" Maple N59W 27.15' "S33 NBT"
 12" Cherry N36E 20.65' "S34 NBT"
 10" Cherry S82E 10.35' "S3 NBT"
 Bearings are magnetic. Distances are to nail with tag. * denotes 1964 NBT.



Signed by Stephan J. Szyszkoski Date 1/9/06
 Surveyor's Michigan License No. 33986
 For the Michigan Department of Natural Resources