

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Schoolcraft	Located In:	Corner Code #
(County)		
1. Public Land Survey	T <u>46N</u> R <u>15W</u>	<u>G6</u>
	T <u>46N</u> R <u>15W</u>	<u>G7</u>
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

May 23 2006

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- (G6) Quarter corner common to Sections 15 and 16. 1960 - Remonumented by Billy D. Buckler RLS from Maple B.T. N63W 35 links. Set 1" pipe with 4" brass cap. 12" Soft Maple N11W 29.5 links, 14" Y.Birch N62E 16.5 links.
 (G7) Corner common to Sections 15-16-21-22. 1960 - Reestablished by double proportionate measurement to the original record by Billy D. Buckler RLS. Set 1" pipe with 4" brass cap. 6" Sugar N22W 38 links, 7" Sugar S40E 21 links, 15" Sugar N56E 77 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (G6) Recovered the 1960 monument leaning and with the cap broken off. Removed the monument and placed a new one at the recovered position and in accord with the 1960 NBTs, now both rotting stumps.
 (G7) Recovered the 1960 monument, which had apparently been driven only about 1' into the ground, in good condition and at record bearing and distance from the 1960 NBTs, all in good condition. Drove the monument deeper into the ground to set firm.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|--|--|
| (G6) Set 1" IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nails in:
8" Maple N32W 8.0' mrkd "1/4S NBT"
11" Maple S63E 12.38' do
6" Maple S57W 8.44' do
11" Maple S17W 25.7' do
Bearings are magnetic. Distances are to nail with tag. * denotes 1960 NBT. | (G7) Found 1" ID I.pipe with 4" brass MI Dept. of Conservation cap. Set measuring nails in:
14" Sugar N18W 24.98' mrkd "S16" *
13" Sugar S40E 14.4' "S22" *
27" Sugar N62E 51.05' "S15" *
5" Balsam S24W 17.07' mrkd "S21 NBT"
Bearings are magnetic. Distances are to nail with tag. * denotes 1960 NBT. |
|--|--|



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 8/15/06