

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Schoolcraft</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T46N R 15W	G 9
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

4. Lot No. _____, Recorded Plat _____
 5. Private Claims

I, Stephan J. Szyszkoski, in a field survey on March 15, 2007 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 (G9) Corner common to Sections 21-22-27-28. 1850 - Established by Guy Carleton, Deputy Surveyor. Set post. Cedar 12 N40W 18 links, Cedar 10 S8E 19 links. 1960 - Corner remonumented by Billy D. Buckler RLS from 12" Cedar stump N40W 18 links. Set 1" pipe with 4" brass cap. 6" Cedar N82W 57.5 links, 8" Cedar S20E 71 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 (G9) Recovered the 1960 monument in good condition and at record bearing and distance from the Cedar NBT NW, in good condition, and from the stump remains of the original BT Cedar NW, with blaze visible. Accepted the monument as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 (G9) Found 1" ID I.pipe with 4" MI Dept. of Conservation cap. Set measuring nails with MDNR tags in the sides of the following trees:
 10" Cedar S89E 10.8' mrkd "S27 NBT"
 10" W.Brich S40E 13.5' "S27 NBT"
 6" Cedar S57W 16.4' "S28 NBT"
 10" Cedar N73W 39.4' open blaze (1960 NBT)
 Bearings are magnetic.

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													



Signed by Stephan J. Szyszkoski Date 10/10/07

Surveyor's Michigan License No. 33986