

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Schoolcraft</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>46N</u> R <u>15W</u>	<u>G10</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims

I, Stephan J. Szyszkoski, in a field survey on Sept. 25, 2007 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(G10) Quarter corner common to Sections 27 and 28. 1850 - Established by Guy Carleton, Deputy Surveyor, midway and on the Section line between Section corners 40.00 chains north and south. Set post. Spruce 8 N55W 13 links, Spruce 6 S35E 16 links. 1960 - Reestablished by Billy D. Buckler RLS midway and on the Section line between Section corners north and south. Set 1" pipe with 4" brass cap. 10" Aspen N75W 117 links, Power Line Pole S46W 40 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(G10) The original post and accessories were not recovered. The 1960 accessories are both gone. Found the 1960 monument disturbed and out of position. Reestablished the corner midway and on the Section line between Section corners 2651.45' north and south. At the position for the corner, I reinstalled the 1960 monument.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(G10) Set 1" ID iron pipe with 4" brass MI Dept. of Conservation cap (1960 monument of record).
 P.Pole #902 S56W 24.92' set nail w/ MDNR tag
 P.Pole #903 S81E 397.15' do
 P.Pole M882 503 N86W 432.31' do
 P.Pole #900 N85W 855.24' do
 Bearings are magnetic. The corner falls on the north side of the power line opening.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													



Signed by Stephan J. Szyszkoski Date 10/10/07

Surveyor's Michigan License No. 33986