

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Schoolcraft</u> (County)	Located In:	Corner Code #
1. Public Land Survey	<u>T46N R 15W</u>	<u>G11</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Stephan J. Szyszkoski, in a field survey on September 19, 2007 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 (G11) Corner common to Sections 27-28-33-34. 1850 - Established by Guy Carleton Deputy Surveyor. Set post. Spruce Pine 8 N31E 20 links, Tamarack 10 N86 1/2W 30 links. Old highway plans for M-28 show: Concrete monument. 2" Tag Alder N68W 5.57', 2" Tag Alder S80E 15.29', 2" Tag Alder N53E 11.50'. Post-construction notes show: "Brass cap on 2" iron pipe. No natural witnesses available. No guard post". 1960 - Corner recovered and recorded by Billy D. Buckler, RLS - 3" pipe with 4" brass cap, State Highway mon. Right of Way Monument (R/W) bears N01E 20 links distant. This corner was set by Highway Department.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 (G11) Recovered the State Highway Dept. monument, a brass State of Michigan cap mounted atop a 2" iron pipe, in good condition and at substantial record bearing and distance from the R/W monument witness noted in the 1960 record. I note that the concrete monument mentioned in the M.S.H.D. plans was likely that set by the USDA Biological Survey in the late 1930's during their monumentation of much of the Seney National Wildlife Refuge boundary. I accept the monument as the best available evidence of the position of the original corner. C/L of M-28 is 86.4' south.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 (G11) Found 2" I.pipe with 4" brass State of MI cap.
 Set measuring nails with MDNR tags in the sides of the following two trees:
 7" Tamarack S82W 109.91' mrkd "S33 NBT"
 9" twin Cherry N57E 47.84' "S27 NBT"
 Guard rail post west end G.R. S62E 148.08' set nail w/tag
 Top center R/W monument N07E 13.4'
 Bearings are magnetic.

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		10		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													



Signed by Stephan J. Szyszkoski Date 10/10/07

Surveyor's Michigan License No. 33986