

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Schoolcraft</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T46N R 15W	H3
	T _____ R _____	_____
	T _____ R _____	_____
	S _____ T _____ R _____	_____
2. Property Controlling in Section	S 15 T46N R 15W	12
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims

12 Jun 27 2006
 H3 Jul 05 2006

I, Stephan J. Szyszkoski, in a field survey on _____, 20__ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(H3) Quarter corner common to Sections 3 and 10. 1850 - Established by Guy Carleton, Deputy Surveyor, midway and on the Section line between Section corners 40.42 chains east and west. Set post. Beech 6 N69E 20 links, Beech 6 S67W 54 links. Found no subsequent record.
 (12-Sec. 15) South 1/16 corner Section 15. Not established in the original survey. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(H3) The original post and accessories were not recovered. Found no evidence of the position of the original corner on the ground. Reestablished the corner midway and on the Section line between Section corners 2652.49' east and west.
 (12-Sec. 15) Established the corner midway and on a straight line between Center of Section 1319.08' north and Quarter corner 1319.08' south.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(H3) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nails in: 5" Beech S46E 4.28' mrkd "1/4S NBT" 9" Maple South 56.75' do 7" Beech S50W 37.2' do 4" Hemlock S88E 17.7' do Bearings are magnetic. Distances are to nail with tag.	(12) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nails in: 6" Hemlock S21W 3.15' mrkd "S1/16 BT" 21" Hemlock S51E 23.85' do 6" Maple N16E 32.55' do 10" Beech S78W 17.92' do Bearings are magnetic. Distances are to nail with tag.
---	--

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3								●					
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7								●					
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 8/15/06

For the Michigan Department of Natural Resources, Office of Land and Facilities