

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

Schoolcraft <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>46NR</u> <u>15W</u>	<u>H4</u>
	T <u>46NR</u> <u>15W</u>	<u>G4</u>
	T <u>    </u> <u>    </u>	<u>    </u>
2. Property Controlling in Section	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
3. Miscellaneous Property in Sec.	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

Jul 05 2006

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 20\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

- (H4) Center of Section 10. Not established in the original survey. Found no subsequent record.
- (G4) Quarter corner common to Sections 9-10. 1850 - Established by Guy Carleton, Deputy Surveyor, midway and on the Section line between Section corners 40.205 chains north and south. Set post. Beech 8 N29W 13 links, Beech 6 S76E 25 links. Found no subsequent record.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

- (H4) Established the corner at the intersection of straight lines connecting opposite 1/4 corners.
- (G4) The original post and accessories were not recovered. Found no evidence of the position of the original corner on the ground. Reestablished the corner midway and on the Section line between Section corners 2652.02' north and south.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

- |   |   |
|---|---|
| (H4) Set 1"IDx36" I.pipe with 4" alum.<br>MDNR cap. Set measuring nails in: | (G4) Set 1"IDx36" I.pipe with 4" alum.<br>MDNR cap. Set measuring nails in: |
| 10" Maple S66W 1.57'      mrkd "CS 8T"                                      | 9" Y.Birch S70E 9.35'   mrkd "1/4S NBT"                                     |
| 14" Hemlock N52W 14.6'   do   | 6" Maple N32E 12.1'     do  |
| 14" W.Pine N20E 17.9'   do  | 7" W.Birch clump N48W 14.68' do   |
| 6" Balsam S87E 6.92'    do  | 9" Maple S55W 26.65'   do   |
| Bearings are magnetic. Distances are to nail with tag.                      | Bearings are magnetic. Distances are to nail with tag.                      |



Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 8/15/06

For the Michigan Department of Natural Resources, Office of Land and Facilities