

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Schoolcraft</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T46N R 15W	H9
	T_____ R_____	_____
	T_____ R_____	_____
2. Property Controlling in Section	S_____ T_____ R_____	_____
	S_____ T_____ R_____	_____
3. Miscellaneous Property in Sec.	S_____ T_____ R_____	_____
	S_____ T_____ R_____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File
Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9								●					
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on March 15, 2007 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
(H9) Quarter corner common to Sections 22 and 27. 1850 - Established by Guy Carleton, Deputy Surveyor, midway and on line between Section corners 40.375 chains east and west. Set post. Fir 6 S84W 5 links, Spruce 10 N44E 12 links. 1960 - Reestablished by Billy D. Buckler, midway and on line between Section corners. Set 1"ID I.pipe with 4" brass cap. 6" W.Birch S88E 7.5 links, 6" Balsam N69W 43.5 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
(H9) Recovered the 1960 monument in good condition and at record bearing and distance from the W.Birch NBT SE, in good condition. Verified the position of the monument and found that it is 1.4' NE of the proportionate position intended in 1960. Accepted the monument as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
(H9) Found 1"ID I.pipe with 4" State of Michigan cap. Set measuring nails with MDNR tags in the sides of the following trees:
6" W.Birch S86W 5.0' mrkd "1/4S NBT"
7" W.Birch N87E 5.35' mrkd "1/4S" (1960 NBT)
8" Tamarack N43W 44.1' mrkd "1/4S NBT"
4" Balsam S14W 3.05' do
Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date 10/10/07

Surveyor's Michigan License No. 33986