

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

<u>Schoolcraft</u> (County)	Located In:	Corner Code #
1. Public Land Survey	<u>T46N R 15W</u>	<u>H 11</u>
	T <u>    </u> R <u>    </u>	<u>    </u>
	T <u>    </u> R <u>    </u>	<u>    </u>
2. Property Controlling in Section	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
3. Miscellaneous Property in Sec.	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
4. Lot No. <u>    </u> , Recorded Plat <u>    </u>		
5. Private Claims		

Register of Deeds Stamp & File  
Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on September 19, 2007 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:  
(H11) Quarter corner common to Sections 27 and 34. 1850 - Established by Guy Carleton, Deputy Surveyor, midway and on the Section line between Section corners 40.37 chains east and west. Set post. Tamarack 4 S56 1/2E 35 links, Tamarack 5 N81 1/2E 77 links. Old M.S.H.D. plans for highway M-28 show: 1.5" pipe [understood to be found prior to construction], 10" Poplar Due East 31.88', 8" Tamarack S06E 29.83', 6" Birch S43W 34.55'. Post-construction: Brass cap on 2" pipe. 12" Spruce N45W 86.90', 12" Poplar N15E 96.4', 10" Aspen Due East 32.0'. 1961 - Billy D. buckler RLS recovered the M.S.H.D. 2" pipe monument with brass cap, noted the MSHD witness 10" Poplar East 31.88' (dead), and made a new witness 4" B. Cherry N02E 27.1' Corner lies 77.5' north of C/L M-28.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
(H11) Recovered the MSHD monument, a 2" iron pipe with 3" brass State of Michigan cap, in good condition, and at record bearing and distance from the 4" B.Cherry NBT of record, found in good condition with overgrown blazes. Found the current C/L of highway M-28 to be 77.9' south. Accepted the monument as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
(H11) Found 2" pipe with 3" brass State of Michigan cap. Set measuring nails with MDNR tags in the sides of the following trees:  
8" Spruce N87W 25.69' mrkd "1/4S NBT"  
8" Cherry N46E 45.23' do  
11" Cherry N19W 44.1' do  
9" twin Cherry N01E 20.06' do  
Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date 10/10/07

Surveyor's Michigan License No. 33986