

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Schoolcraft</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>46N</u> R <u>15W</u>	<u>14</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S <u>14</u> T <u>46N</u> R <u>15W</u>	<u>8</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims

8 Mar 23 2006
 14 Jun 19 2006

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10	●	11		12	
5												
6	18		17		16		15	●	14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- (14) Quarter corner common to Sections 10 and 11. 1850 - Established by Guy Carleton, Deputy Surveyor, midway and on the Section line between Section corners 40.42 chains north and south. Set post. Spruce 8 N85W 21 links, Hemlock 8 N68E 11 links. Found no subsequent record.
- (8-Sec. 14) West 1/16 corner, Section 14. Not established in the original survey. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (14) The original post and accessories were not recovered. Found no evidence of the position of the original corner on the ground. Reestablished the corner midway and on the Section line between Section corners 2648.03' north and south.
- (8-Sec. 14) Established the corner midway and on a straight line between Quarter corner 1337.09' west and the Center of Section 1337.09' east.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|--|--|
| (14) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nails in:
8" Tamarack S02W 11.65' mrkd "1/4S NBT"
8" W.Pine S81E 25.05' do
8" Spruce N24E 20.53' do
10" Spruce N75W 11.48' do
Bearings are magnetic. Distances are to nail with tag. | (8) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nails in:
16" W.Pine N65W 4.7' mrkd "W1/16 BT"
14" W.Pine S20E 17.5' do
9" W.Pine S65E 23.25' do
8" Hemlock N30E 21.45' do
Bearings are magnetic. Distances are to nail with tag. |
|--|--|



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 8/15/06