

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Schoolcraft</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>46N</u> R <u>15W</u>	<u>I 11</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11									●				
12		31		32		33		34		35		36	
13													

I, Stephan J. Szyszkoski, in a field survey on September 19, 2007 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
(I11) Corner common to Sections 26-27-34-35. 1850 - Established by Guy Carleton Deputy Surveyor. Set post. Tamarack 4 S38W 16 links, Tamarack 10 N46E 31 links. 1960 - Corner recovered and recorded by Billy D. Buckler RLS: "This corner was set by U.S. Department of Agriculture Biological Survey. Corner lies 110 links north of C/L of M-28. found 3" concrete [monument] with 3" brass cap". No new witnesses taken. This corner is also shown on old MSHD plans for M-28 as: Concrete monument. 5" Poplar S70W 7.79', 4" poplar N59E 15.28', 4" Poplar S14W 19.27'. Also shown on undated sketch of MSHD: Concrete monument 72.62' north of St. 1210+70.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
(I11) Found the U.S. Biological Survey monument, a 3" concrete cylinder with 3" brass U.S.B.S. cap, in good condition, 73.2' north of the C/L of highway M-28. None of the prior witnesses were recovered. Accepted the monument as the best available evidence of the position of the original corner. I note that the U.S. Biological Survey performed work in the area in the late 1930s, monumenting much of the boundary of the Seney National Wildlife Refuge boundary.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
(I11) Found 3" conc. monument with U.S. Biological Survey cap. Set measuring nails with MDNR tags in the sides of the following three trees:
5" Spruce S72E 36.8' mrkd "S35 NBT"
6" Spruce N24E 15.35' "S26 NBT"
7" W. Birch N24W 22.3' "S27 NBT"
Top center of conc. R/W mon. N06E 27.2'
Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date 10/10/07

Surveyor's Michigan License No. 33986