

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Schoolcraft</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>46N</u> R <u>15W</u>	<u>K6</u>
	T _____ R _____	_____
	T _____ R _____	_____
	S _____ T _____ R _____	_____
2. Property Controlling in Section	S <u>15</u> T <u>46N</u> R <u>15W</u>	<u>10</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Jun 21 2006

I, Stephan J. Szyszkoski, in a field survey on _____, 20__ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(K6) Quarter corner common to Section 13-14. 1850 - Established by Guy Carleton, Deputy Surveyor, midway and on the Section line between Section corners 40.47 chains north and south. Set post. Tamarac 12 N70W 47 links, Spruce 8 S85E 39 links. Found no subsequent record.
 (10-Sec. 15) South 1/16 corner between Sections 15 and 16. Not established in the original survey. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(K6) The original post and accessories were not recovered. Found no evidence of the position of the original corner on the ground. Reestablished the corner midway and on the Section line between Section corners 2616.29' north and south.
 (10-Sec. 15) Established the corner midway and on the Section line between Section corner 1319.38' south and Quarter corner 1319.38' north.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(K6) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nails in: 15" W.Pine S25W 35.45' mrkd "1/4S NBT" 8" W.Pine S71W 34.55' do 17" W.Pine N70W 32.95' do 15" W.Pine N75E 23.05' do Bearings are magnetic. Distances are to nail with tag.	(10) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nails in: 21" Maple S36E 14.15' mrkd "S1/16 BT" 6" Cherry S33W 20.8' do 12" Maple S64E 27.87' do 16" Y.Birch N04E 14.53' do Bearings are magnetic. Distances are to nail with tag.
--	--



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 8/15/06

For the Michigan Department of Natural Resources, Office of Land and Facilities