

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Schoolcraft	Located In:	Corner Code #
(County)		
1. Public Land Survey	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S 3 T 46N R 15W	5
	S 3 T 46N R 15W	9
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

4. Lot No. _____, Recorded Plat _____

5. Private Claims

9 Mar 14 2006

5 Mar 13 2006

I, Stephan J. Szyszkoski, in a field survey on _____, 20__ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- (5-Sec. 3) North 1/16 corner, Section 3. Not established in the original survey. Found no subsequent record.
- (9-Sec. 3) East 1/16 corner, Section 3. Not established in the original survey. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (5-Sec. 3) Established the corner according to the original US plat of this township, 20.157 chains, proportionate to the original record, north of the Center of the Section and on a straight line between the Center 1343.32' south and Quarter corner 1329.60' north.
- (9-Sec. 3) Established the corner midway and on a straight line between Center of Section 1319.43' West and Quarter corner 1319.43' East.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|---|---|
| (5) Set 1"IDx36" I.pipe with 4" alum.
MDNR cap. Set measuring nails in:
11" W.Pine S43W 23.3' mrkd "N1/16 BT"
16" W.Pine N67E 26.8' do
10" W.Pine N16W 10.55' do
14" W.Pine N81E 9.0' do
Bearings are magnetic. Distances are to nail with tag. | (9) Set 1"IDx36" I.pipe with 4" alum.
MDNR cap. Set measuring nails in:
10" W.Pine S58E 37.1' mrkd "E1/16 BT"
5" Tamarack N11E 29.85' do
6" Tamarack N46W 19.45' do
4" W.Pine S30E 14.85' do
Bearings are magnetic. Distances are to nail with tag. |
|---|---|

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4			3		2		1	
3													
4	7		8		9			10		11		12	
5													
6	18		17		16			15		14		13	
7													
8	19		20		21			22		23		24	
9													
10	30		29		28			27		26		25	
11													
12	31		32		33			34		35		36	
13													



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 8/15/06