

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

<u>Schoolcraft</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S <u>3</u> T <u>46N</u> R <u>15W</u>	<u>6</u>
	S <u>10</u> T <u>46N</u> R <u>15W</u>	<u>14</u>
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims

14 Mar 20 2006  
6 Mar 21 2006

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 20\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

- (6-Sec. 3) Northeast 1/16 corner, Section 3. Not established in the original survey. Found no subsequent record.
- (14-Sec. 10) South 1/16 between Sections 10 and 11. Not established in the original survey. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (6-Sec. 3) Established the corner at the intersection of straight lines connecting opposite 1/16 corners.
- (14-Sec. 10) Established the corner midway and on the Section line between Section corner 1324.01' South and Quarter corner 1324.01' North.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- |  |  |
|--|--|
| (6) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nails in:<br>12" W.Pine N78E 15.1' mrkd "NE1/16 BT"<br>6" W.Pine S01W 28.65' do<br>6" Tamarack N65N 20.75' do<br>7" Tamarack S55W 51.8' do<br>Bearings are magnetic. Distances are to nail with tag. | (14) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nails in:<br>20" Maple N87E 12.25' mrkd "S1/16 BT"<br>7" Cherry S25E 36.8' do<br>12" Balsam S21W 27.1' do<br>6" Maple S88W 13.7' do<br>Bearings are magnetic. Distances are to nail with tag. |
|--|--|



Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 8/15/06