

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Schoolcraft</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T ___ R ___ T ___ R ___ T ___ R ___	_____ _____ _____
2. Property Controlling in Section	S ___ T ___ R ___ S 10 T46N R 15W S 14 T46N R 15W	_____ 6 1
3. Miscellaneous Property in Sec.	S ___ T ___ R ___ S ___ T ___ R ___	_____ _____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims

1 Mar 21 2006
 6 Mar 23 2006

I, Stephan J. Szyszkoski, in a field survey on _____, 20__ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

(6-Sec. 10) Northeast 1/16 corner, Section 10. Not established in the original survey. Found no subsequent record.
 (1-Sec. 14) West 1/16 corner between Sections 11 and 14. Not established in the original survey. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(6-Sec. 10) Established the corner at the intersection of straight lines connecting opposite 1/16 corners.
 (1-Sec. 14) Established the corner midway and on the section line between Section corner 1329.89' West and Quarter corner 1329.89' East.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(6) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nails in: 9" Hemlock N71E 99.0' mrkd "NE1/16 BT" 19" Y.Birch S70E 79.75' do 7" Maple N69W 24.45' do 5" Hemlock S88W 32.0' do	(1) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nails in: 10" W.Pine S10W 13.5' mrkd "W1/16 BT" 13" W.Pine N34W 22.7' do 15" W.Pine N41E 17.5' do 7" Cedar S86E 45.4' do
Bearings are magnetic. Distances are to nail with tag.	Bearings are magnetic. Distances are to nail with tag.



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 8/15/06

For the Michigan Department of Natural Resources, Office of Land and Facilities