

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Schoolcraft	Located In:	Corner Code #
(County)		
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S <u>10</u> T <u>46N</u> R <u>15W</u>	<u>10</u>
	S <u>10</u> T <u>46N</u> R <u>15W</u>	<u>12</u>
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5							●	●					
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Jun 27 2006

I, Stephan J. Szyszkoski, in a field survey on _____, 20__ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- (10-Sec. 10) South 1/16 corner between Sections 9 and 10. Not established in the original survey. Found no subsequent record.
- (12-Sec. 10) South 1/16 corner Section 10. Not established in the original survey. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (10-Sec. 10) Established the corner midway and on the Section line between Quarter corner 1326.01' north and Section corner 1326.01' south.
- (12-Sec. 10) Established the corner midway and on a straight line between Center of Section 1325.09' north and Quarter corner 1325.09' south.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|---|--|
| <ul style="list-style-type: none"> (10) Set 1"IDx36" I.Pipe with 4" alum. MDNR cap. Set measuring nails in: 14" Hemlock S66W 16.8' mrkd "S1/16 BT" 7" Hemlock N59W 20.52' do 5" Hemlock N23E 22.93' do 15" Hemlock S41E 24.77' do Bearings are magnetic. Distances are to nail with tag. | <ul style="list-style-type: none"> (12) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nails in: 5" Balsam S27E 8.9' mrkd "S1/16 BT" 12" Cedar West 7.76' do 5" Cedar N57E 24.63' do 13" Cedar S72E 9.0' do Bearings are magnetic. Distances are to nail with tag. |
|---|--|



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 8/15/06

For the Michigan Department of Natural Resources, Office of Land and Facilities