

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Schoolcraft</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T____ R____	_____
	T____ R____	_____
	T____ R____	_____
2. Property Controlling in Section	S____ T____ R____	_____
	S 14 T 46N R 15W	10
	S 3 T 46N R 15W	13
3. Miscellaneous Property in Sec.	S____ T____ R____	_____
	S____ T____ R____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims

Mar 23 2006

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3									●				
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7									●				
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

(10-Sec. 14) South 1/16 corner between Sections 14 and 15. Not established in the original survey. Found no subsequent record.
 (13-Sec. 3) Southeast 1/16 corner, Section 3. Not established in the original survey. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(10-Sec. 14) Established the corner midway and on the Section line between Section corner 1319.70' south and Quarter corner 1319.70' north.
 (13-Sec. 3) Established the corner at the intersection of straight lines connecting opposite 1/16 corners.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(10) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nails in: 9" Hemlock S69E 9.75' mrkd "S1/16 BT" 8" Hemlock S07W 20.55' do 8" Hemlock N55W 11.3' do 6" Spruce N36E 6.3' do Bearings are magnetic. Distances are to nail with tag.	(13) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nails in: 6" Spruce N62E 4.0' mrkd "SE1/16 BT" 10" Tamarack S71E 32.65' do 10" Tamarack N63W 12.65' do 4" Tamarack S12W 9.95' do Bearings are magnetic. Distances are to nail with tag.
---	--



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 8/15/06