

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Schoolcraft</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S <u>11</u> T <u>46N</u> R <u>15W</u>	<u>11</u>
	S <u>11</u> T <u>46N</u> R <u>15W</u>	<u>8</u>
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Mar 20 2006

I, Stephan J. Szyszkoski, in a field survey on _____, 20 ____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(11-Sec. 11) Southwest 1/16 corner, Section 11. Not established in the original survey. Found no subsequent record.
 (8-Sec. 11) West 1/16 corner, Section 11. Not established in the original survey. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(11-Sec. 11) Established the corner at the intersection of straight lines connecting opposite 1/16 corners.
 (8-Sec. 11) Established the corner midway and on a straight line between Quarter corner 1328.77' West and Center of Section 1328.77' East.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(11) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nails in: 12" W.Birch S04N 5.55' mrkd "S1/16 BT" 8" W.Birch S69W 13.85' do 10" Balsam N70W 14.0' do 8" Balsam N09E 12.7' do Bearings are magnetic. Distances are to nail with tag.	(8) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nails in: 8" Cedar S12W 5.7' mrkd "W1/16 BT" 8" Cedar S88E 7.15' do 10" Cedar N58W 8.7' do 12" Cedar S88W 9.75' do Bearings are magnetic. Distances are to nail with tag.
---	---

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 8/15/06