

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

| | | |
|------------------------------------|---------------------------------------|---------------|
| <u>Schoolcraft</u> (County) | Located In: | Corner Code # |
| 1. Public Land Survey | T ___ R ___ | _____ |
| | T ___ R ___ | _____ |
| | T ___ R ___ | _____ |
| | S <u>27</u> T <u>46N</u> R <u>15W</u> | <u>11</u> |
| 2. Property Controlling in Section | S <u>27</u> T <u>46N</u> R <u>15W</u> | <u>15</u> |
| | S ___ T ___ R ___ | _____ |
| 3. Miscellaneous Property in Sec. | S ___ T ___ R ___ | _____ |
| | S ___ T ___ R ___ | _____ |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Stephan J. Szyszkoski, in a field survey on September 24, 2007 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

| | | | | | | | | | | | | | |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
| | A | B | C | D | E | F | G | H | I | J | K | L | M |
| 1 | | | | | | | | | | | | | |
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | | |
| 11 | | | | | | | ● | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | | |
| 13 | | | | | | | | | | | | | |

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 (11-Sec. 27) Southwest 1/16 corner, Sec. 27. Not established in the original survey.

(15-Sec. 27) West 1/16 corner between Sections 27 and 34. Old highway plans of Highway M-28 by Michigan State Highway Dept. show Brass cap on 2" iron pipe. 10" Aspen N15W 19.13', 14" Aspen N05E 59.40', 4" Aspen N50E 26.40'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 (11-Sec. 27) Established the corner at the intersection of straight lines connecting opposite 1/16 corners.

(15-Sec. 27) Established the corner midway and on the Section line between Section corner 1332.43' west and Quarter corner 1332.43' east. From the position thus established, I found the M.S.H.D. brass cap on 2" iron pipe, in good condition, 7.90' west, which I did not accept as marking the position for the corner. The C/L of M-28 is approx. 82.0' South.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

| | |
|--|---|
| (11) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nails with MDNR tags in the sides of the following trees: 12" Aspen S20W 19.97' mrkd "SW1/16 BT" 12" Aspen S47E 25.5' do 5" Aspen S50W 23.3' do 6" Balsam S85W 40.23' do Bearings are magnetic. | (15) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nails with MDNR tags in the sides of the following trees: 6" J.Pine N06E 24.71' mrkd "W1/16 BT" 10" J.Pine N15W 45.78' do 6" J.Pine N41E 33.98' do State of MI monument N84W 7.90' Bearings are magnetic. |
|--|---|



Signed by Stephan J. Szyszkoski Date 10/10/07

Surveyor's Michigan License No. 33986