

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Schoolcraft</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
	S <u>28</u> T <u>46N</u> R <u>15W</u>	<u>16</u>
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Stephan J. Szyszkoski, in a field survey on September 24, 2007 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 (16-Sec. 28) East 1/16 corner between Sections 28 and 33. Not established in the original survey. Old highway plans for M-28 from Michigan State Highway Dept. show 4" sq'd post replaced with 2" pipe with brass cap. 12" J.Pine N5W 55.10', 12" J.Pine N21E 54.13', 6" J.Pine N59E 50.87'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 (16-Sec. 28) Established the corner midway and on the Section line between Quarter corner 1345.09' west and Section corner 1345.09' east. From the position thus established, I found the M.S.H.D. monument, in good condition, S60W, 8.44' distant, which I did not accept as marking the position for the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 (16) Set 5/8"x18" rebar driven into a J.Pine root capped with a plastic cap stamped "MI DNR LS33986"
 Power Pole 4615/28R23 N80W 41.96' nail w/tag
 9" J.Pine S36W 1.0' nail w/tag
 Top center ROW marker N30W 15.2'
 Brass cap "State of Michigan" mon. S60W 8.44' (buried below surface of ground). Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date 10/10/07

Surveyor's Michigan License No. 33986