

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

Schoolcraft <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T 46N R 15W	F7
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S 21 T 46N R 15W	14
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5			4		3		2		1	
3													
4	7		8			9		10		11		12	
5													
6	18		17			16		15		14		13	
7						●							
8	19		20			21		22		23		24	
9								●					
10	30		29			28		27		26		25	
11													
12	31		32			33		34		35		36	
13													

I, Stephan J. Szyszkoski, in a field survey on 14 09/15/2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

(F7) Quarter corner common to Sections 16 and 21. 1850 - Established by Guy Carleton Deputy Surveyor midway and on the Section line between Section corners 40.11 chains east and west. Set post. Hemlock 17" S42W 24 links, Hemlock 22" N58W 17 links. 1960 - Reestablished by Billy D. Buckler RLS midway and on line between Section corners. Set 1" iron pipe with 4" brass cap. 12" Soft Maple S60E 32.5 links, 18" W.Pine S58W 47 links.

(14-Sec. 21) South 1/16 corner between Sections 21 and 22. Not established in the original survey.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(F7) Found the 1960 monument in good condition and at record bearing and distance from the 1960 NBTs. The Soft Maple SE is in decline, the W.Pine SW is in good condition. Found the monument to be N21E 1.9' from the midway position intended in 1960 and accepted same as a careful and faithful reestablishment of the position of the original corner.

(14-Sec. 21) Established the corner midway and on the Section line between Quarter corner 1317.48' north and Section corner 1317.48' south.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

(F7) Found 1"ID I.pipe with 4" brass MI Dept. of Conservation cap. Set measuring nail with MDNR tag in the side of:  
 30" W.Pine S66W 32.0' 1960 NBT  
 9" Maple S41E 9.52' mrkd "1/4S NBT"  
 9" Hemlock N57E 18.05' do  
 20" Hemlock N88W 43.05' do  
 Bearings are magnetic.

(14) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:  
 8" Balsam N62W 16.3' mrkd "S1/16 BT"  
 7" W.Birch N12W 33.3' do  
 8" triple W.Birch N05E 38.15' do  
 8" Y.Birch N25E 30.9' do  
 Bearings are magnetic.

Signed by *Stephan J. Szyszkoski*  
 Surveyor's Michigan License No. 33986

Date 10/02/2008



For the Michigan Department of Natural Resources, Office of Land and Facilities