

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Schoolcraft	Located In:	Corner Code #
(County)		
1. Public Land Survey	T 46N R 15W	E8
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S 21 T 46N R 15W	1
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Stephan J. Szyszkoski, in a field survey on E8 08/11/2008
1 09/10/2008 do hereby state
that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2
above were in conformance with regulations and rules therefore as required in the current manual of survey
instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of
a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with
the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established,
re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(E8) Quarter corner common to Sections 20 and 21. 1850 - Established by Guy Carleton Deputy Surveyor midway and on the Section line between Section corners 40.26 chains north and south. Set post. Spruce 4" N52W 12 links, Spruce 5" N42E 5 links. 1960 - Reestablished by Billy D. Buckler RLS midway and on line between Section corners. Set 1"ID I.pipe with 4" brass cap. 12" Cedar N03E 34.5 links, 10" Cedar S87W 30 links.

(1-Sec. 21) West 1/16 corner between Sections 16 and 21. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(E8) Found the 1960 monument in good condition and at record bearing and distance from the 1960 witnesses, now both dead with markings visible. The position of the monument is S72E 1.7' from the midway position intended in 1960 and I accept same as a careful and faithful reestablishment of the position of the original corner.

(1-Sec. 21) Established the corner midway and on the Section line between Section corner 1328.24' west and Quarter corner 1328.24' east.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(E8) Found 1"ID I.pipe wth 4" brass MI Dept. of Conservation cap. Set measuring nail with MDNR tag in the side of:
9" B.Spruce N04W 6.81' mrkd "1/4S NBT"
11" Cedar S24E 20.1' do
11" Cedar S63E 15.64' do
7" W.Birch N70W 24.57' do
Bearings are magnetic.

(1) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
9" Hemlock N76E 14.28' mrkd "W1/16 BT"
7" Hemlock S57E 19.25' do
8" Y.Birch N88W 21.25' do
7" Maple N52W 29.69' do
Bearings are magnetic.

Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 10/02/2008



For the Michigan Department of Natural Resources, Office of Land and Facilities