

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Schoolcraft <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T 46N R 15W	G8
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S 21 T 46N R 15W	13
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21	●	22		23		24	
9							●						
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Stephan J. Szyszkoski, in a field survey on G8 08/11/2008 do hereby state
13 09/15/2008
that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2
above were in conformance with regulations and rules therefore as required in the current manual of survey
instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of
a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with
the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established,
re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded
on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:
(G8) Quarter corner common to Sections 21 and 22. 1850 - Established by Guy Carleton Deputy Surveyor
midway and on the Section line between Section corners 40.00 chains north and south. Set post.
Hemlock 10" S60E 17 links, Hemlock 14" N55W 25 links. 1954 - Remonumented by Billy D. Buckler RLS -
"This corner was pointed out to me by Carl Lensi, of Northwestern Co. One original B.T. still in
place, in poor condition". Set 1" pipe with 4" brass cap. 10" Hard Maple N72W 19 links, 12" Hard
Maple S25E 52 links.

(13-Sec. 21) Southeast 1/16 corner, Section 21. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
(G8) Found the 1954 monument in good condition. The 1954 witnesses were not recovered. The position
of the monument is N57W 3.6' from the midway position between adjacent Section corners and I accept
same as a careful and faithful perpetuation of the position of the original corner.

(13-Sec. 21) Established the corner at the intersection of straight lines connecting opposite 1/16
corners.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
(G8) Found 1"ID I.pipe with 4" brass MI Dept.
of Conservation cap. Set measuring nail with
MDNR tag in the side of:
10" Spruce N39W 15.3' mrkd "1/4S NBT"
10" twin Spruce N39E 27.4' do
4" W.Birch S74E 31.06' do
5" Cherry N78E 9.52' do
Bearings are magnetic.

(13) Set 1"IDx36" I.pipe with 4" alum. MDNR cap.
Set measuring nail with MDNR tag in the side of:
12" Balsam N56E 5.25' mrkd "SE1/16 BT"
6" Maple S14E 13.18' do
5" Spruce S67W 25.41' do
8" W.Birch N59W 16.15' do
Bearings are magnetic.

Signed by *Stephan J. Szyszkoski* Date 10/02/2008
Surveyor's Michigan License No. 33986
For the Michigan Department of Natural Resources, Office of Land and Facilities

