

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

# LAND CORNER RECORD

T. 46 N. R. 16W


Schoolcraft COUNTY

DESCRIPTION OF CORNER Sec. Cor. common to Secs. 5, 6, 7 and 8.

CORNER MONUMENT 1" Pipe with 4" Aluminum Cap.

DATE MONUMENT PLACED AND WITNESSED 6-5-63.

WITNESSES TO CORNER..... 9" W. Spruce (S. 7 N.B.T.) S. 24° W., 37½ Lks.



6" W. Spruce (S. 8 N.B.T.) S. 66° E., 20 Lks.

18" W. Pine (S. 5 N.B.T.) North 70 Lks.

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was replaced from one probable B.T., a Tamarack bearing N. 31° W., 40 Lks. Position checks with corners in all directions.

SURVEYOR'S SEAL

SIGNED Billy D. Buckles DATE 11/26/63  
REGISTERED LAND SURVEYOR