

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 46 N.R. 16 & 17 W.


Alger & Schoolcraft COUNTY

DESCRIPTION OF CORNER Section corner for: Secs. 24 and 19, T.46 N. R.16 W.
Secs. 25 and 30, T.46 N. R.17 W.

CORNER MONUMENT 1" Iron pipe with 4" Aluminum Cap.

DATE MONUMENT PLACED AND WITNESSED 6/13/63

WITNESSES TO CORNER..... 6" Cedar (S. 25) (N.B.T.), S.17°W., 32½ Lks.



7" Cedar (S. 24) (N.B.T.), N.43°W., 30½ Lks.

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was set by single proportionate measurement
along Township Line. No original evidence.

SURVEYOR'S SEAL

SIGNED *Billy D. Buckler*
Billy D. Buckler DATE 7-26-63
REGISTERED LAND SURVEYOR